



ADDENDUM NO. 1

DATE: JANUARY 6, 2020

BID NO. 2838

**CLOVIS EAST HIGH SCHOOL CTE FARM AND FOOD PRODUCT FACILITY
CLOVIS UNIFIED SCHOOL DISTRICT
CLOVIS, CALIFORNIA**

FILE NO. 10-H3
APPL. NO. 02-118543

G.A. PROJECT NO. 1739

NOTICE TO ALL CONTRACTORS SUBMITTING BIDS FOR THIS WORK AND TO ALL PLAN HOLDERS:

You are hereby notified of the following changes, clarifications or modifications to the original Contract Documents, Project Manual, Drawings, Specifications and subsequent Addenda. This Addendum shall supersede the original Contract Documents, and previous Addenda wherein it contradicts the same and shall take precedence over anything to the contrary therein. All other conditions remain unchanged.

INDEX OF ADDENDA TRANSMITTED HEREWITH

Addendum Item AD1-A01 thru AD1-A10

AD1-A01: **BID DATE REVISION:**
Refer to Notice To Contractors in project manual.

Change bid date to read “11:00 A.M. on January 28, 2021”.

Due to COVID, bids will not be opened in public. Bid tabulation and sub-contractor information will be posted on website 24-48 hours after bid opening.

AD1-A02: **DVBE REVISION:**
Refer to Spec Section Notice to Contractors, DVBE Declaration of Good Faith Efforts.

Incorporate the following DVBE Revision into the Notice to Contractors:

DVBE Declaration of Good Faith Efforts and any related DVBE documents to be included with sealed bid and delivered to Clovis USD Purchasing, 1450 Herndon Avenue, Clovis, CA 93611 on or before January 22, 2021. NO paperwork is to be submitted to Construction Services. ALL Bids and DVBE paperwork to be sealed and filed at Clovis USD Purchasing 1450 Herndon Avenue, Clovis, CA 93611 on or before January 22, 2021.

AD1-A03:

ARCHITECTURAL DRAWINGS & SPECS:

Refer to Sheets A2.1, A2.2, A3.1 and Spec. Section 07-410 Metal Panels.

1. Prefinished Metal Panels vs. Field Painted Sheet Metal Clarification:

Prefinished Metal Panels apply at:

- A. Metal Standing Seam Roofing, Ridge, Rake, Gutter and downspout and related misc. flashing and trim; plus overhang, cap, fascia and underside, Detail 16/A6.3.
- B. Box Rib Metal Siding, Ceiling, Parapet Cap, Gutter and Downspout and related flashing and trim including Detail 2/A6.2 at exterior overhang; plus scupper-conductor/downspout Detail 9/A6.4.
- C. Architect will select a maximum of 2 colors for each metal panel type.

2. Field Painted Sheet Metal apply at all other sheet metal work not noted above.

AD1-A04:

EPOXY FLOORING:

Refer to Sheet A2.1, Floor Plan.

1. Extend epoxy flooring with 6" coved base under Demonstration Desk sink and kneespace in Room #1. Extend flooring with 6" coved base under Demonstration Desk gas range area and sink; plus at student station sinks and gas ranges in Room #2.
2. Install epoxy flooring with 6" coved base in janitorial closet located at intersection of grid lines 4 & F.

AD1-A05:

ABRASIVE WALK-OFF CARPET:

Refer to Sheet A2.1, Floor Plan.

Contractor to install abrasive walk-off carpet within Room #1 for all exterior doors; at each double door (7'-0" x 3'-0") and (3'-6" x 3'-0") at the single door. The abrasive walk-off carpet is Owner provided and Contractor installed. Contractor to provide vinyl transitional mouldings between carpet and epoxy flooring.

AD1-A06:

OPENING SCHEDULE REVISION:

Refer to Opening Schedule on Sheet A7.1

Door Opening #3 and #4 shall use Hardware Group #1F.

AD1-A07:

FINISH HARDWARE SCHEDULE REVISION:

Refer to Spec Section 08-700, Finish Hardware.

Replace pages 4, 5 and 6 of the Spec Section 08-700, Finish Hardware Schedule with the attached revised Finish Hardware Schedule.

AD1-A08:

JANITORIAL CLOSET DOOR OPENING NUMBER CLARIFICATION:

Refer to Floor Plan, Sheet A2.1, Janitorial Closet.

The Door opening number for the door located at the Janitorial Closet at the southeast corner of building should be Opening #11; in lieu of #10.

AD1-A09: EXTERIOR FINISH SCHEDULE REVISION:

Refer to Exterior Finish Schedule, Sheet A7.1.

Cement Plaster & All cement plaster metal elements shall be paint type EP-2; in lieu of EP-3.

AD1-A10: FURRED WALL CLARIFICATION

Refer to Floor Plan, Sheet A2.1, Room #3 Dry Storage

The north wall of the Room #3 Dry Storage shall be a furred wall with gyp bd. finish constructed with 2x6 studs so electrical panels will be flush with wall finish.

END OF ADDENDUM

FINISH HARDWARE SCHEDULE:

HARDWARE MANUFACTURERS:	MFR #
HAGER.....	HGR
SCHLAGE.....	SCH
LCN.....	LCN
TRIMCO.....	TRI
PEMKO.....	PEM
SARGENT.....	SAR
VON DUPRIN.....	VON
MCKINNEY.....	MCK
GLYNN JOHNSON.....	GLY
IVES.....	IVES

GROUP #1:

6	HINGE	BB1199 4.5x4.5 NRP	32D	HGR
1	EXIT DEVICE	AX-99L-F X 499F	26D	VON
1	EXIT DEVICE	AX-99EO-F X 499F	26D	VON
1	MULLION	KR4954	SP28	VON
2	GLASS BEAD KIT	99GBK-R	SP28	VON
1	RIM CYLINDER	20-057 ICX	626	SCH
2	MORTISE CYLINDER	20-061 ICX XQ11-948	626	SCH
1	MORTISE CYLINDER	20-061 ICX (MULLION)	626	SCH
4	CORE	23-030	626	SCH
2	DOOR CLOSER	4111EDA	689	LCN
2	KICK PLATE	K0050 10" X 2" LDW	630	TRI
1	OVERHEAD HOLDER	100H @ BACK TO BACK DOORS	32D	GLY
1	DOOR STOP/ HOLDER	PER DETAIL		
1	THRESHOLD	PER DETAIL		
2	DOOR BOTTOM	PER DETAIL		
1	HEAD SEAL	2891AS		PEM
2	JAMB SEAL	290AS		PEM
1	MULLION SEAL	5110BL120		PEM

**08-700
FINISH HARDWARE
PAGE 5**

GROUP #1F:

6	HINGE	BB1199 4.5x4.5 NRP	32D	HGR
1	EXIT DEVICE	AX-CD-99NL	26D	VON
1	EXIT DEVICE	AX-CD-99DT	26D	VON
1	MULLION	KR4954	SP28	VON
1	RIM CYLINDER	20-057 ICX	626	SCH
1	MORTISE CYLINDER	20-061 ICX (MULLION)	626	SCH
2	CORE	23-030	626	SCH
2	DOOR CLOSER	4111EDA	689	LCN
2	KICK PLATE	K0050 10" X 2" LDW	630	TRI
1	OVERHEAD STOP	100S @ LHR DOOR 4	32D	GLY
2	DOOR STOP	1209	626	TRI
1	THRESHOLD	PER DETAIL		
2	DOOR BOTTOM	PER DETAIL		
1	HEAD SEAL	2891AS		PEM
2	JAMB SEAL	290AS		PEM
1	MULLION SEAL	5110BL120		PEM

GROUP #2:

3	HINGE	BB1199 4.5x4.5 NRP	32D	HGR
1	EXIT DEVICE	AX-CD-99NL	26D	VON
1	GLASS BEAD KIT	99GBK-R	SP28	VON
1	RIM CYLINDER	20-057-ICX	626	SCH
1	MORTISE CYLINDER	20-061-ICX XQ11-948	626	SCH
2	CORE	23-030	626	SCH
1	DOOR CLOSER	4111EDA	689	LCN
1	KICK PLATE	K0050 10" X 2" LDW	630	TRI
1	DOOR STOP	PER DETAIL		
1	THRESHOLD	PER DETAIL		
1	DOOR BOTTOM	PER DETAIL		
1	HEAD SEAL	2891AS		PEM
2	JAMB SEAL	290AS		PEM

GROUP #3:

3	HINGE	BB1199 4.5x4.5 NRP	32D	HGR
1	LOCKSET	L9485P 06A L283-722 L583-363	626	SCH
1	CLOSER	4011 REG	689	LCN
1	KICK PLATE	K0050 10" X 2 LDW	630	TRI
1	WALL STOP	1270CVSV	626	TRI
1	THRESHOLD	PER DETAIL		
1	DOOR BOTTOM	PER DETAIL		

**08-700
FINISH HARDWARE
PAGE 6**

GROUP #4:

3	HINGE	BB1199 4.5 x 4.5 NRP	32D	HGR
1	LOCKSET	ND53PD RHO	626	SCH
1	CLOSER	4011 REG	689	LCN
1	KICK PLATE	K0050 10" X 2" LDW	630	TRI
1	FLOOR STOP	1211	626	TRI
1	THRESHOLD	PER DETAIL		
1	DOOR BOTTOM	PER DETAIL		
1	HEAD SEAL	2891AS		PEM
2	JAMB SEAL	290AS		PEM

GROUP #5:

3	HINGE	BB1199 4.5 x 4.5 NRP	32D	HGR
1	LOCKSET	ND80PD RHO	626	SCH
1	OVERHEAD HOLDER	100H	32D	GLY
1	THREHOLD	PER DETAIL		
1	DOOR BOTTOM	PER DETAIL		

END OF SECTION