

ADDENDUM NO. 5

DATE: 02/17/2022

PROJECT:

CLOVIS WEST HIGH SCHOOL - AQUATIC IMPROVEMENTS
1070 E Teague Ave
Fresno, CA 93720
CUSD Bid No 2875

OWNER:

CLOVIS UNIFIED SCHOOL DISTRICT
1450 Herndon Ave
Clovis, CA 93612

ARCHITECT:

DARDEN ARCHITECTS, INC.
Attention:
6790 N. West Avenue
Fresno, California 93711
T. (559) 448-8051
F. (559) 446-1765



DARDEN PROJECT NO. 1944
DSA File Nos. 10-H3
DSA APPL. NO. 02-119318

It will be the responsibility of the General Contractor to submit the information contained in this addendum to all its subcontractors and suppliers. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

The following additions, deletions, and revisions to the SHEETS and Project Manual are hereby made and do become a part of these Contract Documents.

PROJECT:

ADDENDUM NO. 5..... DATE: 02/17/2022
PAGE 2

INDEX OF ADDENDA TRANSMITTED HEREWITH

PROJECT MANUAL:

BIDDING AND CONTRACT REQUIREMENTS:

CHANGES TO PRIOR ADDENDAAD5-CPA01
CHANGES TO BIDDING REQUIREMENTSAD5-CBR01

ATTACHMENTS:

DOCUMENTS OR SPECIFICATIONS:

PRE BID RFI LOG (Page 1)

PROJECT MANUAL:

BIDDING AND CONTRACT REQUIREMENTS:

CHANGES TO PRIOR ADDENDA:

AD5-CPA01 Refer to Addendum No.1 Item AD1-CCC01:

1. Refer to BIDDING AND CONTRACT DOCUMENTS, "NOTICE TO CONTRACTORS"
Page 4 for change in Bid Date
2. Omit the following text:

"before 11:00 a.m. on February 23, 2022"

3. Replace omitted text with the following:

"before 1:00 p.m. on March 4, 2022"

CHANGES TO BIDDING REQUIREMENTS:

AD5-CBR01 Refer to Project Manual:

1. Add the attached PRE BID RIF LOG identified with a AD5 on the upper right-hand corner.

END OF ADDENDUM NO. 5



MARK WILSON
CONSTRUCTION

Prebid Request for Information Log

Project: CWHS Aquatic Improvements Pre-Bid Log							
RFI #	Trade	Drawing / Spec	Questions	Date	Addenda	Architect's Response	Date
001	Steel	X/S102	Page X/S102 detail J14. Item #11 calls for the steel to be prime painted. Item #12 calls for any steel exposed to the weather is to be hot dip galv. The steel columns on this project are not covered, do they need to be hot dip galv. or prime painted? Please advise.	1/27/2022	AD2 & AD3	<p>Due to cost reductions the steel will not be painted and the MCM Panels omitted.</p> <p>All exterior steel will be hot dipped galvanized after fabrication. At the Field Weld locations provide two (2) coats of 97% pure zinc metallic flake, which leaves 94% zinc in the dry film. Refer to Specifications under STEEL AND FABRICATIONS, 3.5 Repair / Restoration.</p> <p>The Custom Perforated Metal Panels in the front of the shade structure shall be Powder Coated After Fabrication; and fit up in the field.</p>	1/27/2022
002	Steel	SD/A502, SD/A503	The Guard Rails, Handrails, etc are to be Hot Dipped Galvanized after fabrication. Can these also have the option to be either hot dipped galvanized - or- stainless steel?	1/27/2022		<p>Yes.</p> <p>If a Stainless Steel Railing Fabricator wants to bid this project, the stainless steel option is acceptable for all railings / guardrails, etc.</p>	1/27/2022
003	Demolition	024919 - SELECTIVE DEMOLITION	Since many of the utilities are to be removed, will any Hydro-Evacuation for soil excavation (Badger hydrovac) be required to exposed existing utilities that may remain in place and not get removed?	1/27/2022		<p>Yes.</p> <p>An Existing PG&E line runs under the pool deck in the N-S direction, under or adjacent the pool storage rooms and west of the dive / play pools. This PG&E utility line will require hydrovac soil excavation, and also back-filled with a lean concrete sand mix once exposed.</p> <p>Another area that should be exposed is the south side of the pool equipment room where the utilities are entering this building and exterior utility yard.</p>	1/27/2022
004	Steel	A4/SDA502, J8/SDA502	½" x ½" x 11 gauge square is called out for the pickets at the railings. This size is not made. The thickest wall size available is 16 gauge (.065 wall) Please clarify what to use.	2/3/2022		Detail to modified and call out ¾" x ¾" x 11 gauge square tube in lieu of ½" x ½" x 11 gauge.	2/4/2022
005	Demolition, Concrete, Electrical	SD/E102	Concrete around the scoreboard is shown as not being removed on the plans. Electrical contractor will have to get a new underground conduit for power and data. Does Electrical scope need to include saw cutting demo and patch back or will this be added to the Demo and concrete scope.	2/7/2022		Demolition scope to be under CWPOOL-1. Concrete work to be under CWPOOL-2. This scope will NOT be included under electrical. However, after speaking with district, we will leave the (E) conduit in place, so omit work here.	2/8/2022

